BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

APPROVED SCHEDULE - B

Issued to :

Original / Duplicate
Item No.

Name of the Work: Improvements to Roads, Drains and Covering Slab at Chamundeshwari Layout 5th Main Road Left Side in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Rates Quoted by Contractor	
				In Figures	In Words
1	266.76	Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	105.84	Rupees One Hundred Five and Eighty Four Paise Only
2	37.05	Providing and laying in position **plain cement concrete of mix 1:4:8 with OPC cement @ 180 Kgs** using **40mm** and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, **in foundation and plinth**, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4847.04	Rupees Four Thousand Eight Hundred Forty Seven and Four Paise Only
3	592.80	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for **vertical surface** such as **walls at any thickness**, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	292.68	Rupees Two Hundred Ninety Two and Sixty Eight Paise Only
4	81.51	Providing and laying in position **reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works **in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall** (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	6065.28	Rupees Six Thousand Sixty Five and Twenty Eight Paise Only
5	65.21	Providing **mild steel reinforcement for R.C.C** work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work	Qtl	7975.80	Rupees Seven Thousand Nine Hundred Seventy Five and Eighty Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka, B.B.M.P.
Bangalore - 560 092

Sl. No.	Approved Qty.	Description	Unit	Rates Quoted by Contractor	
				In Figures	In Words
6	222.30	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	642.60	Rupees Six Hundred Forty Two and Sixty Paise Only
7	1236.00	Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) etc complete as per specifications and directions of engineer in charge of the work	m	32.40	Rupees Thirty Two and Forty Paise Only
8	222.30	Providing two line dressing to granite stone slab / granite stone masonry etc complete as per specifications and directions of engineer in charge of the work	Sqm	851.04	Rupees Eight Hundred Fifty One and Four Paise Only
9	240.08	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	73.57	Rupees Seventy Three and Fifty Seven Paise Only

I am prepared to execute the above mentioned work written by me in Schedule - B

Contractor Signature
Reg. No.
Postal Address

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92